

**Irrigation Water Supply Well Construction Project  
Project 2020-05-FGC**

**Pre-Bid Questions - Addendum #2**

The following Questions were asked in regards to this project. The Districts response is found to the right.

Question

Response

1	Is there a Bid Bond? There is nothing in the paperwork that would indicate this	Correct. The successful bidder shall be required to execute a Material and Labor Payment Bond and Performance Bond issued by a corporate surety, acceptable to the Sunrise Recreation and Park District, for the IRRIGATION WATER SUPPLY WELL CONSTRUCTION PROJECT AT FOOTHILL GOLF COURSE. Each bond shall not be less than one hundred percent (100%) of that portion of the contract price.
2	Are you requiring a non witness performance testing of the pump	No, just the testing on site to confirm operation
3	We recommend using 8x12 SRI Silica as gravel pack, is this acceptable?	This is open to changes with submittals by the successful bidder.
4	The conductor shows 25' in the specification and then shows 60' on the bid form, which is the correct length required?	Conductor casing and sanitary seal would be 25'
5	The specifications call out A53 for the 10" casings, it only comes in .250, .365, &.3125 would be Roscoe Moss A139 and almost double the cost of A53 .250 wall. Is .250 A53 acceptable? If not would .375 wall be acceptable	ASTM -A53 Grade B steel with .365" wall would be acceptable
6	The specifications detail the contractor to have stamped engineered drawings for the pump portion of the project. Is this negotiable?	Bidders will not need stamped engineered drawings however drawings will need to be approved and warranted for proper well operation for at least one year.
7		
8		
9		
10		