

**1st Phase Park Improvements Project - Cabana Park
Project 2019-2-CA**

Pre-Bid Walk Questions - Addendum #2 Page 1 of 2

The following Questions were asked in regards to this project. The Districts response is found to the right.

Question

Response

<p>1 What type fabric was used to cover the pool deck</p>	<p>US Fabric 160NW - See the specifications below. If fabric is damaged, it shall be repaired by contractor with US Fabric 160NW or approved equal.</p>
---	---

PROPERTY	TEST METHOD	ENGLISH	METRIC
Weight - Typical	ASTM D-5261	6.0 oz/sy	203 g/sm
Tensile Strength	ASTM D-4632	160 lbs	711 N
Elongation @ Break	ASTM D-4632	50%	50%
Mullen Burst*	ASTM D-3786*	305 psi	2,103 kPa
Puncture Strength*	ASTM D-4833*	90 lbs	400 N
CBR Puncture	ASTM D-6241	410 lbs	1,824 N
Trapezoidal Tear	ASTM D-4533	60 lbs	267 N
Apparent Opening Size	ASTM D-4751	70 US Sieve	0.212 mm
Permittivity	ASTM D-4491	1.50 Sec-1	1.50 Sec-1
Water Flow Rate	ASTM D-4491	110 g/min/sf	4,480 l/min/sm
UV Resistance @ 500 Hours	ASTM D-4355	70%	70%

<p>2 Was the pool deck level?</p>	<p>The pool Deck was completely removed and disposed off site. The pool bottom was not level. If you mean was the rubble that was covered by the fabric level? - It was relatively level, plus or minus 6"</p>
-----------------------------------	--

<p>3 It has been verified that the ATT contact will be Conner Fisher 916 - 484 - 2373 he stated that ATT will modify the specifications. (normally 4" conduit is used see District Response for the updated specification)</p>	<p>The Specifications for the ATT conduit is modified as follows: Schedule 40 - 2" PVC conduit with long sweeps and 36" cover at finished grade, located in a straight line from pole UD063715 to pole UD064635. Length of conduit = 250' + one pull box with traffic lid marked either "ATT" or "communication".</p>
--	---

<p>4 The installation of the Decomposed Granite after the fence and concrete paving may cause damage to the paving.</p>	<p>Include the cost installing the Decomposed Granite as an additive alternate. Use the new bid sheet 2 of 7 (b) provided</p>
---	---

5 Who installs Dog waste dispensers?

Dog waste dispensers will be provided and installed by the District

6 Who installs the Park Rules sign?

Park rules sign will be provided and installed by the District