

**Irrigation Water Supply Well Construction Project  
Project 2020-05-FGC**

**Pre-Bid Questions - Addendum #1**

The following Questions were asked in regards to this project. The Districts response is found to the right.

Question	Response
1 Where are the plans to the project?	The District has re-sent both plans and specifications to all contractors. In addition the documents are posted on the District Website ( <a href="http://www.sunriseparks.com">www.sunriseparks.com</a> )
2 What is the VFD rated for?	The electrical power is rated at 208V, the District has agreed to reduce the expected 400GPM to 325GPM due to the fact that the largest submersible pump available for this rating is 30HP which can supply 325GPM.
3 Can we re-use the old column, it appears to be in decent shape?	Yes, the District is in favor of re-using any of the materials that appear to be in acceptable condition.
4 Can we use a submersible test pump	Yes
5 We recommend using 8x12 SRI Silica as gravel pack, is this acceptable?	Wood Rodgers will review all submittals for approval
6	
7	
8	
9	
10	